
PI: 2.001
1:13
1:120
Level
Chainage 00.000 05.000 10.000 15.000 20.000 25.000 29.192
Existing Levels 23.999 23.991 23.980 23.978 23.998 23.904 23.729
Proposed Levels 24.064 24.189 24.147 24.106 24.064 24.022 23.987
Horizontal Geometry L =2.001 L =27.191
Vertical Geometry G =7.500% L =2.000 G =-0.833% L =27.192
Surface Water CL
Surface Water IL
Surface Water Details
Foul Water CL
Foul Water IL
Foul Water Details

PD 12 - LONGSECTION
SCALE: H 1:250,V 1:50. DATUM: 20.000


PI: 2.000
1:13
1:100
Level
Chainage 00.000 05.000 08.804
Existing Levels 23.911 23.878 23.864
Proposed Levels 23.961 24.081 24.043
Horizontal Geometry L =2.000 L =6.804
Vertical Geometry G =7.500% L =2.000 G =-1.000% L =6.804

PD 13 - LONGSECTION
SCALE: H 1:250,V 1:50. DATUM: 20.000


PVI STA: 29.607
PVI ELEV: 24.219
K: 9.000
LVC: 14.997
PI: 2.000
PI: 2.250
PI: 8.888
BVCS: 22.108
BVCE: 24.281
PC: 23.992
Mid: 26.799
PT: 29.607
PC: 36.970
EVCS: 37.105
EVCE: 24.281
Mid: 41.310
LP CH: 29.608m
LV: 24.250m
1:13
1:120
1:120
Level
Chainage 00.000 05.000 10.000 15.000 20.000 25.000 30.000 35.000 40.000 45.650
Existing Levels 24.062 24.062 24.057 24.061 24.078 24.095 24.108 24.130 24.146 24.235
Proposed Levels 24.299 24.424 24.382 24.341 24.299 24.262 24.250 24.266 24.306 24.353
Horizontal Geometry L =2.000 0.250 L =6.638 L =15.104 R: 12.750 L: 5.615 L =7.363 R: 17.777 L: 8.680
Vertical Geometry G =7.500% L =2.000 G =-0.833% L =20.108 R =900.000 K =9.000 L =14.997 G =0.833% L =8.545

PD 14 - LONGSECTION
SCALE: H 1:250,V 1:50. DATUM: 20.000


PI: 2.000
1:13
1:100
Level
Chainage 00.000 05.000 10.000 13.109
Existing Levels 23.711 23.744 23.797 24.062
Proposed Levels 23.824 24.004 24.054 24.085
Horizontal Geometry L =2.000 L =11.109
Vertical Geometry G =7.500% L =2.000 G =1.000% L =11.109

PD 15 - LONGSECTION
SCALE: H 1:250,V 1:50. DATUM: 20.000


PVI STA: 15.000
PVI ELEV: 24.046
K: 6.001
LVC: 10.000
PI: 2.000
PC: 2.518
Mid: 7.411
BVCS: 10.000
BVCE: 24.087
PC: 12.308
Mid: 16.947
EVCS: 20.000
EVCE: 24.087
PT: 21.581
LP CH: 15.001m
LV: 24.066m
1:13
1:120
1:120
Level
Chainage 00.000 05.000 10.000 15.000 20.000 25.000 30.000 35.063 35.600
Existing Levels 23.734 23.779 23.836 23.806 23.774 23.739 23.707 23.713 23.713
Proposed Levels 24.004 24.129 24.087 24.066 24.087 24.129 24.171 24.213 24.212
Horizontal Geometry L =2.000 0.518 R: 40.292 L: 9.787 L =0.008 R: 40.787 L: 9.268 L =13.483
Vertical Geometry G =7.500% L =2.000 G =-0.833% L =8.000 R =600.120 K =6.001 L =10.000 G =0.833% L =15.063

PD 16 - LONGSECTION
SCALE: H 1:250,V 1:50. DATUM: 20.000


CH 0.000
LV 23.711
PI: 2.000
1:13
1:120
Level
Chainage 00.000 05.000 10.000 15.000 20.000 25.000 30.000 35.000 40.000 45.000 50.000 55.000 60.000 65.000 67.528
Existing Levels 23.540 23.489 23.500 23.467 23.434 23.397 23.385 23.384 23.365 23.320 23.280 23.241 23.207 23.189 23.180
Proposed Levels 23.711 23.836 23.795 23.753 23.711 23.670 23.628 23.586 23.545 23.503 23.461 23.420 23.378 23.336 23.315
Horizontal Geometry L =2.000 L =65.528
Vertical Geometry G =7.500% L =2.000 G =-0.833% L =65.528

PD 17 - LONGSECTION
SCALE: H 1:250,V 1:50. DATUM: 20.000

GENERAL SAFETY NOTES:

1. WHERE THE BASE (ROAD BASE) HAS BEEN USED AS A TEMPORARY RUNNING SURFACE DURING THE CONTRACT IT SHALL BE THOROUGHLY CLEANED AND POWER WASHED AS NECESSARY. AFTER DRYING AND IMMEDIATELY BEFORE THE BINDER COURSE IS LAID A TACK COAT OF BITUMEN EMULSION CLASS A1-40 OR K1-40 TO BS434 SHALL BE APPLIED AT A RATE OF 0.35-0.55 LITRES/SQ METER.
2. ALL RADIUS KERBS WITH A RADIUS OF 12m OR LESS SHALL BE FORMED WITH PROPRIETARY RADIUS KERBS.

HEALTH & SAFETY:

1. CONTRACTOR SHOULD BE AWARE OF GENERAL CONSTRUCTION RISKS TO PREVENT SLIPS, TRIPS AND FALLS AND TAKE NECESSARY PRECAUTIONS WITHOUT SPECIAL INSTRUCTION.

ROADS & DRAINAGE

2. CONTRACTOR TO PROVIDE TRENCH SUPPORTS AS APPROPRIATE AND ENSURE THAT PLANT REMAINS A SAFE DISTANCE FROM TRENCHES PRIOR TO INSTALLING DRAINAGE
3. THE TIME THAT EXCAVATIONS ARE OPEN ON SITE SHOULD BE KEPT TO A MINIMUM AND ALL TRENCHES SHOULD BE SURROUNDED BY A BARRIER.
4. CONNECTIONS TO EXISTING SEWERS TO BE MADE BY APPROVED CONTRACTOR ONLY.
5. CONTRACTOR TO MAKE OPERATIVES AWARE OF ASSOCIATED DANGERS TO HEALTH SUCH AS LEPTOSPIROSIS (WEILS DISEASE) AND RECOMMENDED PRECAUTIONS. ADEQUATE WELFARE FACILITIES AND PROTECTIVE CLOTHING TO BE PROVIDED AS REQUIRED.
6. UNFINISHED MANHOLES MUST BE COVERED WITH LOAD BEARING MATERIALS AND SURROUNDED WITH BARRIER.

PIPES & CABLES

7. CONTRACTOR TO OBTAIN ALL SERVICE RECORDS PRIOR TO WORKS COMMENCING.
8. SERVICE RECORDS TO BE REFERRED TO PRIOR TO WORK COMMENCING. CONTRACTOR TO PROCEED WITH CAUTION AND SERVICES TO BE LOCATED BY HAND DIG AND PROTECTED ACCORDINGLY.

EXCAVATION/FILL

9. CONTRACTOR TO ENSURE RELEVANT MEASURES ARE TAKEN TO KEEP PLANT AND PEOPLE A SAFE DISTANCE FROM STEEP SLOPES DURING THE WORKS.
10. CONTRACTOR TO ENSURE THAT PROCEDURES ARE IN PLACE TO KEEP PEOPLE A SAFE DISTANCE FROM WORKING PLANT WHERE NECESSARY.
11. CONTRACTOR TO REFER TO GROUND INVESTIGATION REPORT FOR CONTAMINATION TESTS AND TO PROVIDE ADEQUATE WELFARE FACILITIES AND PROTECTIVE CLOTHING AS REQUIRED.

DRAINAGE SPECIFICATIONS WATER COMPANY

1. ALL ADOPTABLE DRAINAGE WORKS AND MATERIALS TO BE IN ACCORDANCE WITH "SEWERS FOR ADOPTION" 6TH EDITION, THE RELEVANT BRITISH/EUROPEAN AND WATER COMPANIES STANDARDS/REQUIREMENTS/ADDENDUM TO THE MECHANICAL AND ELECTRICAL SPECIFICATION AND KITEMARKED.
2. MANHOLE COVERS SHALL/MUST HAVE A CLEAR OPENING OF 600MM AND SHALL BE CLASS D400 TO BS EN 124 WITH 150MM DEEP FRAMES IN HIGHWAYS.
3. FILLED GROUND MUST BE FILLED AND CONSOLIDATED UNDER THE SUPERVISION AND TO THE SATISFACTION OF WATER COMPANY BEFORE ANY SEWER WORKS ARE CARRIED OUT.
4. ALL ADOPTABLE SEWERS TO BE KITEMARKED (CERTIFIED TO WIS 4-35-01 AND BS/EN13476).
5. PLASTIC CHANNEL SECTIONS IN MANHOLES ARE NOT ACCEPTABLE AND THE WATER AUTHORITY PREFER CLAYWARE CHANNEL IN MANHOLES. PLASTIC CHANNELS ARE DIFFICULT TO SET IN CONCRETE BECAUSE THEY FLOAT AND A SATISFACTORY FINISH CANNOT BE OBTAINED ON THE BENCHING.
6. THE WATER AUTHORITY IS NOT OBLIGED TO ACCEPT FILTER DRAIN/LAND DRAINAGE RUN-OFF INTO THE PUBLIC SEWER NETWORK OR ADOPTABLE DRAINAGE SYSTEM (DIRECTLY OR IN-DIRECTLY). AN ALTERNATIVE METHOD OF DISPOSAL OF THE LAND DRAINAGE RUN-OFF WILL THEREFORE BE REQUIRED AND YOU WILL HAVE TO LIAISE WITH THE LOCAL AUTHORITY, LAND DRAINAGE SECTION WITH REGARD TO THE DISPOSAL OF THE FILTER DRAIN/LAND DRAINAGE RUN-OFF.
7. OVER SLABS MUST CARRY THE BSI KITEMARK OR WILL BE REJECTED BY WATER COMPANY INSPECTOR. WHERE THE CLEAR OPENING OF THE KITEMARKED PRODUCT IS DIFFERENT TO THAT OF THE COVER AND FRAME, A LOADING BEARING SLAB SHOULD BE FITTED ABOVE THE COVER SLAB TO BRING THE SIZE DOWN TO 600MM X 600MM FOR THE WATER COMPANY SPECIFIED COVER SIZE. PLEASE REFER TO CONCRETE PIPE SYSTEMS ASSOCIATION (CPSA), 'TECHNICAL BULLETIN' ISSUED AUTUMN 2004 FOR KITEMARKED COVER SLAB OPENING SIZES.
8. SULPHATE RESISTANT CEMENT (C20-DC2) AND PRECAST CONCRETE PRODUCTS MUST BE USED OR A LABORATORY REPORT PROVIDED PROVING THAT SUCH PRECAUTIONS ARE NOT NECESSARY.
9. THE ADOPTABLE SEWERS SHOULD BE A MINIMUM OF 1M AND MANHOLES 0.5M FROM KERB FACES AND SERVICE MARGINS.
10. "SEWERS MUST HAVE 5 METRES CLEARANCE FROM TREES AND HEDGES (PLEASE ALSO REFER TO FIGURE 2.3 ON PAGE 33 IN "SEWERS FOR ADOPTION" 6TH EDITION FOR RESTRICTIONS ON TREE PLANTING ADJACENT TO SEWERS)".
11. SEWERS TO BE LAID IN CLASS "S" BEDDING (150MM GRANULAR BED AND SURROUND). WHERE DEPTH OF COVER TO TOP OF THE SEWER IS LESS THAN 1.2M IN HIGHWAYS AND VERGES (OR LESS THAN 900MM IN NONE VEHICULAR ACCESS AREAS) THEN A CONCRETE SLAB SHOULD BE PROVIDE ABOVE GRANULAR BED AND SURROUND.
12. BEDDING AND BACKFILL MATERIAL TO CONFORM TO THE REQUIREMENT OF WATER INDUSTRY SPECIFICATION 4-08-02 (TABLE A2).
13. THE CHAMBER SIZE OF MANHOLES WITH MORE THAN ONE CONNECTION IN THEM MAY NEED TO BE INCREASED AN INCREMENT TO ACCOMMODATE THE CONNECTIONS AND BENDS.
14. WATER COMPANY POLICY IS NOT TO ACCEPT TYPE "C" BRICK MANHOLES AND 1050MM DIA MANHOLE RINGS. INSTEAD IT IS PREFERRED THAT YOU USE A TYPE "B" MANHOLE WITH 1200MM DIA OR 1500MM DIA RINGS, WITH THE OPENING SITED OVER THE CHANNEL WHERE DEPTH OF COVER TO PIPE SOFFIT IS 1 - 1.5M.
15. ALL PRIVATE DRAINAGE WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH BUILDING REGULATIONS 2002 EDITION.
16. CONTRACTOR TO ESTABLISH POSITION SIZE AND DEPTH OF ALL EXISTING SEWERS AND SERVICES PRIOR TO COMMENCEMENT ON SITE.
17. THE CONTRACTOR SHALL ALLOW FOR THE PROTECTION, TEMPORARY AND PERMANENT SUPPORT, AND TEMPORARY AND PERMANENT DIVERSION WORKS, AS NECESSARY TO ALL EXISTING SERVICES.
18. THE CONTRACTOR SHALL ALLOW FOR ALL TRAFFIC MANAGEMENT IN CONNECTION WITH ROAD AND SEWER WORKS.
19. THE CONTRACTOR SHALL ALLOW FOR KEEPING SEWER TRENCHES AND EXCAVATIONS AS DRY AS PRACTICABLE BY PUMPING FROM TEMPORARY SUMPS AND DEWATERING AS APPROPRIATE. THE POINT AND METHOD OF DISCHARGE TO BE AGREED WITH THE DRAINAGE AUTHORITY.
20. FOR PIPE SPECIFICATION PLEASE REFER TO ADDITIONAL NOTES.
21. VITRIFIED CLAY PIPES AND FITTINGS SHALL COMPLY WITH THE RELEVANT PROVISIONS OF BS EN295 AND BS 65 RESPECTIVELY AND BE KITEMARKED. ALL PIPES SHALL BE EXTRA STRENGTH TO BS 65 OR EQUIVALENT BS EN295 PIPE CRUSHING STRENGTH.
22. STRUCTURED WALL PLASTIC PIPES TO WIS 4-35-01 MAY BE USED FOR FOUL & SURFACE WATER DRAINAGE, SUBJECT TO ADOPTING AUTHORITY APPROVAL.
23. PRECAST CONCRETE PRODUCTS SHALL COMPLY WITH THE RELEVANT PROVISIONS OF BS 5911 AND BE KITEMARKED. CONCRETE PIPES TO BE CLASS 120 UNLESS NOTED OTHERWISE.
24. GULLY GRATES AND FRAMES SHALL COMPLY WITH THE RELEVANT PROVISIONS OF BS EN124 AND BE OF A NON-ROCKING DESIGN WITH CAPTIVE HINGE ACCESS AND BE KITEMARKED. LOAD CLASS D400 FOR ROADS AND SERVICE YARD AREAS. CLASS C250 TO BE USED IN CAR PARKING AREAS.
25. BACKFILLING AND REINSTATEMENT TO TRENCHES IN PUBLIC HIGHWAYS SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS AND SPECIFICATIONS OF THE ADOPTING AUTHORITY, OR, IN THE ABSENCE OF SUCH, IN ACCORDANCE WITH THE REQUIREMENTS OF "THE STREET WORKS REGULATIONS 1992" AND RELEVANT PROVISIONS OF H.A.U.C. "SPECIFICATION FOR THE REINSTATEMENT OF OPENINGS IN HIGHWAYS" JUNE 1992, BOTH UNDER SECTION 71 OF THE NEW ROADS AND STREET WORKS ACT 1991.
26. ALL TRADITIONAL RAINWATER PIPE DOWN COMERS TO DISCHARGE TO TRAPPED GULLIES.
27. ALL SIPHONIC DRAINAGE DOWN COMERS TO MANUFACTURER SPECIFICATION.
28. ALL ROAD GULLIES ARE TO BE TRAPPED GULLIES.
29. ALL GULLY LEADS TO BE 150mm DIAMETER.
30. ALL REDUNDANT EXISTING DRAINAGE TO BE GRUBBED UP OR GROUTED, ANY EXISTING LIVE DRAINAGE SHOULD BE REPORTED TO THE ENGINEER AND RECONNECTED.
31. ALL ROAD GULLIES & LEADS TO BE CLEARED OF DEBRIS UPON COMPLETION OF WORKS.
32. THE CONTRACTOR MUST ENSURE THAT ANY OF THE EXISTING DRAINAGE WHICH IS LIVE IS KEPT CLEAR OF DEBRIS AND SHOULD ALLOW FOR JETTING THROUGH THE NEW & EXISTING DRAINAGE UPON COMPLETION.
33. CONTRACTOR TO TAKE MEASURES TO PROTECT HIS OPERATIVES WITH RESPECT TO THE PRESENCE OF GAS IN SEWER TRENCHES AND MANHOLES THROUGH THE USE OF GAS MONITORING EQUIPMENT AND BREATHING APPARATUS AS REQUIRED.
34. CONTRACTOR TO APPLY FOR SEWER PERMITS AND ROAD OPENING PERMITS AS NECESSARY FROM THE APPROPRIATE AUTHORITIES, PRIOR TO COMMENCING WORKS.
35. ADOPTABLE PLASTIC SEWER PIPES TO BE LAID IN MAXIMUM 3m LENGTHS UNLESS THERE IS A SPECIFIC OPERATIONAL NEED TO LAY LONGER LENGTHS.
36. WHERE PLASTIC PIPES ARE INSTALLED PRIOR TO GETTING APPROVAL THEN A LIGHT LINE CCTV SURVEY AND REPORT ARE REQUIRED PRIOR TO APPROVAL.

DESIGN NOTES:

1. ALL WORKS TO COMPLY WITH CURRENT VERSION OF THE FOLLOWING DOCUMENTS:
- DESIGN MANUAL FOR ROADS AND BRIDGES (DMRB)
- SPECIFICATION FOR HIGHWAY WORKS (SHW)
- LOCAL AUTHORITY DESIGN GUIDE AND SPECIFICATION
2. PRIOR TO COMMENCING WORKS THE CONTRACTOR SHOULD INVESTIGATE AND LOCATE AS NECESSARY ANY STATUTORY UNDERTAKERS EQUIPMENT WITHIN THE NEW ACCESS AND DISCUSS REQUIREMENTS FOR LOWERING/DIVERSION AND PROTECTION WITH THE RELEVANT UNDERTAKER.
3. ALL WORKS WITHIN THE PUBLIC HIGHWAY TO MEET LOCAL AUTHORITY REQUIREMENTS. CONTRACTOR TO APPLY FOR ROAD OPENING NOTICES ETC AS REQUIRED.
4. CBR VALUE NOT AVAILABLE. ROAD CONSTRUCTION DETAIL SUBJECT TO CONFIRMATION OF CBR VALUES. CONTRACTOR TO ALLOW FOR LAB TESTS TO BE UNDERTAKEN IN AGREEMENT WITH LOCAL AUTHORITY HIGHWAY ENGINEER PRIOR TO WORKS COMMENCING.
5. PROPOSED LEVELS HAVE BEEN BASED ON THE EXISTING TOPOGRAPHICAL SURVEY RECEIVED **JUNE 2020**.
6. PROPOSED DRAWING BASED ON ARCHITECTURAL LAYOUT FROM DEVELOPER RECEIVED **JUNE 2020**.
7. SLOPES GREATER THAN 1 IN 6 MAY REQUIRE STABILISATION. GEOTECHNICAL ENGINEER TO BE CONTACTED TO CONFIRM REQUIREMENTS

DRAINAGE NOTES:

1. ALL PIPES 100Ø UNLESS OTHERWISE STATED.
2. ALL PRIVATE TO ADOPTABLE CONNECTIONS 150Ø UNLESS OTHERWISE STATED.
3. ALL PPIC'S IN TRAFFICKED AREAS TO HAVE D400 COVERS & CONCRETE SURROUND.
4. ALL INTERNAL PLOT DRAINAGE REQUIRES CONFIRMATION PRIOR TO CONSTRUCTION.
5. CONTRACTOR TO CONFIRM MH COVER & INVERT LEVEL OF PROPOSED CONNECTION POINT PRIOR TO CONSTRUCTION. ANY VARIATION TO BE REPORTED TO ENGINEER.
6. THE INVERT LEVEL OF THE EXISTING SEWERS ARE TO BE VERIFIED PRIOR TO COMMENCEMENT OF ANY DRAINAGE WORKS. ANY DISCREPANCY MUST BE NOTIFIED TO THE ENGINEER.
7. EXISTING MANHOLES TO BE MODIFIED TO ACCOMMODATE THE PROPOSED LATERAL CONNECTIONS. CONTRACTOR TO APPLY TO THE WATER AUTHORITY FOR THE SECTION 106 APPROVAL TO MAKE THE CONNECTIONS. PIPES ARE TO BE LAID WITH COMMON INVERT LEVELS.
8. ALL STUB PIPES ARE TO BE CAPPED.
9. ALL PIPES CONNECTIONS TO BE SOFFIT TO SOFFIT UNLESS STATED OTHERWISE. REFER TO MANHOLE SCHEDULE FOR FURTHER INFORMATION.
10. ALL PROPOSED FILTER DRAINS TO CONNECT BACK INTO PLOT DRAINAGE.
11. STONE FILLED LAND DRAINS REQUIRED IN BACK GARDENS WHERE FALLING TOWARDS PROPERTY
12. FLOOD DEFENSE WORKS APPLICATION OR EQUIVALENT TO BE MADE TO THE LOCAL AUTHORITY PRIOR TO CARRYING OUT ANY WORKS TO THE EXISTING WATERCOURSE.

PIPE MATERIALS

- **150-225Ø: UPVC PIPES TO BE BSI KITEMARKED AND CERTIFIED TO WIS 4-35-01 & BS/EN13476.**
- **300-900Ø: CONCRETE PIPES TO BE BSI KITEMARKED, CLASS 120 CONCRETE & CERTIFIED TO BS5911 & 1916.**


CH 0.000
LV 23.232
PVI STA: 38.621
PVI ELEV: 23.086
K: 12.184
LVC: 20.000
PI: 2.000
BVCS: 28.621
BVCE: 23.167
PC: 36.387
Mid: 42.139
PT: 47.891
EVCS: 48.621
EVCE: 23.170
LP CH: 38.467m
LV: 23.127m
1:13
1:124
1:120
Level
Chainage 00.000 05.000 10.000 15.000 20.000 25.000 30.000 35.000 40.000 45.000 50.000 55.000 60.000 64.056
Existing Levels 22.894 22.899 22.909 22.922 22.935 22.958 22.984 23.009 23.032 23.054 23.078 23.114 23.142 23.164
Proposed Levels 23.232 23.358 23.317 23.277 23.237 23.196 23.157 23.132 23.128 23.145 23.181 23.223 23.264 23.298
Horizontal Geometry L =2.000 L =34.387 R: 7.324 L: 11.504 L =16.165
Vertical Geometry G =7.500% L =2.000 G =-0.808% L =26.621 R =1218.430 K =12.184 L =20.000 G =0.833% L =15.435

PD 18 - LONGSECTION
SCALE: H 1:250,V 1:50. DATUM: 20.000


CH 0.000
LV 22.837
PVI STA: 11.400
PVI ELEV: 23.081
K: 5.681
LVC: 10.000
PI: 2.000
BVCS: 6.400
BVCE: 23.031
PI: 10.500
PC: 14.136
EVCS: 16.400
EVCE: 23.043
Mid: 16.5
PCC: 18.942
Mid: 21.345
PRC: 23.747
Mid: 25.546
PCC: 27.344
Mid: 30.352
PRC: 33.359
Mid: 36.493
PT: 39.626
HP CH: 12.108m
LV: 23.060m
1:13
1:100
1:132
Level
Chainage 00.000 05.000 10.000 15.000 20.000 25.000 30.000 35.000 40.000 45.000 46.396
Existing Levels 22.620 22.615 22.607 22.597 22.584 22.568 22.590 22.634 22.675 22.660
Proposed Levels 22.837 23.017 23.056 23.052 23.016 22.978 22.941 22.903 22.865 22.827 22.817
Horizontal Geometry L =2.000 L =8.500 L =3.636 R: 25.000 L: 4.806 R: 25.000 L: 4.806 R: 25.000 L: 3.597 R: 25.000 L: 6.015 R: 25.466 L: 6.267 L =6.770
Vertical Geometry G =7.500% L =2.000 G =1.005% L =4.400 R =568.126 K =5.681 L =10.000 G =-0.755% L =29.996

PD 19 - LONGSECTION
SCALE: H 1:250,V 1:50. DATUM: 20.000


PI: 2.000
1:13
1:60
Level
Chainage 00.000 05.000 10.000 15.000 20.000 25.000 30.000 34.883
Existing Levels 23.074 23.054 23.028 23.003 22.962 22.904 22.845 22.795
Proposed Levels 23.428 23.528 23.445 23.361 23.278 23.195 23.111 23.030
Horizontal Geometry L =2.000 L =32.883
Vertical Geometry G =7.500% L =2.000 G =-1.667% L =32.883

PD 20 - LONGSECTION
SCALE: H 1:250,V 1:50. DATUM: 20.000


PVI STA: 19.243
PVI ELEV: 23.572
K: 6.500
LVC: 10.831
PI: 2.000
BVCS: 13.827
BVCE: 23.527
EVCS: 24.658
EVCE: 23.527
PC: 27.173
Mid: 29.214
PT: 31.255
PC: 32.255
Mid: 33.238
PT: 34.221
PC: 42.525
Mid: 43.508
PT: 44.492
PC: 45.492
Mid: 47.533
PT: 49.573
HP CH: 19.242m
LV: 23.549m
1:13
1:120
1:120
Level
Chainage 00.000 05.000 10.000 15.000 20.000 25.000 30.000 35.000 40.000 45.000 50.000 51.838
Existing Levels 23.089 23.102 23.115 23.126 23.137 23.149 23.139 23.100 23.107 23.143 23.197 23.212
Proposed Levels 23.278 23.453 23.495 23.535 23.549 23.524 23.482 23.440 23.399 23.357 23.315 23.300
Horizontal Geometry L =2.000 L =25.173 R: 9.750 L: 4.082 L =1.000 R: 5.250 L: 1.967 L =8.303 R: 5.250 L: 1.967 L =1.000 R: 9.750 L: 4.082 L =2.265
Vertical Geometry G =7.500% L =2.000 G =0.833% L =11.827 R =649.990 K =6.500 L =10.831 G =-0.833% L =27.180

PD 21 - LONGSECTION
SCALE: H 1:250,V 1:50. DATUM: 20.000

KEY

– – – – –	EXISTING LEVELS
——	PROPOSED LEVELS
——	PROPOSED ADOPTED SW
——	PROPOSED ADOPTED FW
······	PROPOSED HIGHWAY DRAINAGE

SUBJECT TO LOCAL AUTHORITY & WATER AUTHORITY APPROVAL

Date	Revisions	Drawn	Checked	Rev
08/04/2025	LEVELS AMENDED. LONGSECTIONS AMENDED TO SUIT.	JS	AGM	6
20/12/2024	DESIGN TAKEN BACK TO TENDER STAGE.	LM	AGM	5
16/10/2023	SECTIONS UPDATED TO SUIT LATEST SITE LAYOUT.	AM	AE	4
07/07/2023	ROAD 51 UPDATED TO SUIT REVISED LAYOUT	AM	AE	3
22/04/2022	SECTIONS UPDATED TO TENDER DESIGN	LM	AGM	2
03/07/2020	FIRST ISSUE	AGM	AE	1

Dwg Status TENDER

NORTH EAST
0191 2585632

YORKSHIRE
0113 535 3500

RWO
CONSULTING ENGINEERS
WWW.RWO.GROUP
INFO@RWO.GROUP

Client
TAYLOR WIMPEY &
BARRATT HOMES

Project
NORTON LODGE

Title
LONGSECTIONS
SHEET 15 OF 18

DO NOT SCALE	Scale @ A0: 1:250	Drawn AGM	Checked AE	Date 02.07.2020
Job No 19185		Dwg No D314		Rev 6