

[illegible]

DESIGN NOTES:

1. ALL WORKS TO COMPLY WITH CURRENT VERSION OF THE FOLLOWING DOCUMENTS:
 - a. DESIGN MANUAL FOR ROADS AND BRIDGES (DMR)
 - b. SPECIFICATION FOR HIGHWAY WORKS (SHW)
2. LOCAL AUTHORITY DESIGN GUIDE (LADG)
3. PRIOR TO COMMENCING WORKS THE CONTRACTOR SHOULD INVESTIGATE AND LOCATE AS NECESSARY AN STATUTORY UNDERGROUNDS EQUIPMENT WITHIN THE NEW ACCESS AND DISCONTINUE ANY FURTHER LOW VOLTAGE OVERHEADS AND PROTECTION WITH THE RELEVANT UNDERGROUNDS. ALL WORKS WITHIN THE PUBLIC HIGHWAY TO MEET LOCAL AUTHORITY REQUIREMENTS.
4. CONTRACTOR TO APPLY FOR ROAD OPENING NOTICES ETC AS REQUIRED.
5. CONTRACTOR TO APPLY FOR LOW VOLTAGE DISCONTINUATION ETC, SUBJECT TO CONFIRMATION OF VALUES. CONTRACTOR TO ALLOW FOR LAB TESTS TO BE UNDERTAKEN IN AGREEMENT WITH LOCAL AUTHORITY HIGHWAY ENGINEER PRIOR TO WORKS COMMENCING.
6. PROPOSED LEVELS HAVE BEEN BASED ON THE EXISTING TOPOGRAPHICAL SURVEY RECEIVED ON **JUNE 2020**.
7. PROPOSED DRAWINGS BASED ON ARCHITECTURAL, LAYOUT FROM DEVELOPER RECEIVED **JUNE 2020**.
8. SLOPES GREATER THAN 1 IN 4 MAY REQUIRE STABILISATION. GEOTECHNICAL ENGINEER TO BE CONTACTED TO CONFINED FILL REQUIREMENTS.

DRAINAGE NOTES:

1. ALL PIPES 100% UNLESS OTHERWISE STATED.
2. ALL PRIVATE TO ADAPTABLE CONNECTIONS 150 UNLESS OTHERWISE STATED.
3. ALL PIPES IN TRAFFIC AREAS HAVE TO HAVE DADA CURBS & CONCRETE SURROUND.
4. ALL PIPES IN DRAINAGE AREAS TO BE VERIFIED PRIOR TO CONSTRUCTION.
5. CONTRACTOR TO CONFIRM MANHOLE & INVERT LEVEL, OR PROPOSED CONNECTION POINT TO CONSTRUCTION, ANY VARIATION TO BE REPORTED TO ENGINEER.
6. IN THE EVENT OF THE EXISTING WORKS BEING TO BE VERIFIED PRIOR TO COMMENCEMENT ANY CRANAGE WORKS, ANY DISCREPANCY MUST BE NOTIFIED TO THE ENGINEER.
7. EXISTING MANHOLES TO BE MODIFIED TO ACCOMMODATE THE PROPOSED LAYOUT.
8. 1200MM DIA. OF THE EXISTING WORKS ARE TO BE VERIFIED PRIOR TO CONSTRUCTION APPROVAL. TO MAKE THE CONNECTIONS. PIPES ARE TO BE LAID WITH COMMON INVERT LEVEL.
9. ALL STUB PIPES ARE TO BE CAPPED.
10. ALL PIPES TO BE LAID TO A SLOPE UNLESS OTHERWISE STATED, REFER TO MANHOLE SCHEDULE FOR FURTHER INFORMATION.
11. ALL PROPOSED FILL DRAGS TO CONNECT BACK TO EXISTING INLET TO PLOT DRAINAGE.
12. ALL EXISTING PIPES TO BE VERIFIED PRIOR TO CONSTRUCTION, ANY VARIATION TO BE REPORTED TO THE ENGINEER.
13. FLOOD DEFENSE WORKS APPLICATION OR EQUIVALENT TO BE MADE TO THE LOCAL AUTHORITY PRIOR TO CARRYING OUT ANY WORKS TO THE EXISTING WATERCOURSE.

- 150-2250: UPVC PIPES TO BE BSI KITEMARKED AND CERTIFIED TO WS 6-35-01 & BS EN 13476
- 300-3600: CONCRETE PIPES TO BE BSI KITEMARKED, CLASS 120 CONCRETE & CERTIFIED TO BS 5911 & 1916.

KEY

----- EXISTING LEVELS

----- PROPOSED LEVELS

----- PROPOSED ADOPTED SW

----- PROPOSED ADOPTED FW

----- PROPOSED HIGHWAY DRAINAGE

**SUBJECT TO LOCAL AUTHORITY &
WATER AUTHORITY APPROVAL**

08/04/2025	LEVELS AWARDED. LONGSECTIONS AMENDED TO SUIT.	JS	AGM
20/12/2024	DESIGN TAKEN BACK TO TENDER STAGE.	LM	AGM
16/03/2023	SECTIONS UPDATED TO SUIT LATEST SITE LAYOUT.	AM	AE
22/04/2022	SECTIONS UPDATED TO TENDER DESIGN	LM	AGM
03/07/2020	FIRST ISSUE	AGM	AE
Date	Revisions	Drawn	Checked

NORTH EAST 019 2556332	
YORKSHIRE 0115 330 3002	CONSULTING ENGINEERS WWW.RWQ-GROUP.COM INFO@RWQ-GROUP.COM
Client TAYLOR WIMPEY & BARRATT HOMES Project NORTON LODGE Title LONGSECTIONS SHEET 18 OF 18	
DO NOT SCALE Scale of 1:120	Drawn D317
job No 19185	Checked AE Date: 02.07.07 Rev: 5